EXTERNAL WORKS:

- DEEP CLEAN ALL EXTERNAL WALL SURFACES TO FASCIA HEIGHT AND REMOVE ANY GRAFFITI
- CLEAN GLAZING INTERNALLY AND EXTERNALLY
- REMOVE EXISTING VERTICAL STYLE WINDOW BLINDS.
- RELOCATE LETTERBOX TO OLD ATM POSITION
- REMOVE ALL UNSIGHTLY WEEDS
- REPAINT HANDRAILS
- PREPARE AND REDECORATE ALL EXISTING WINDOW FRAMES
- RELOCATE EXISTING ATM FROM KING STREET TO SALEM STREET ELEVATION
- MAKE GOOD STONEWORK / FIXINGS AROUND OLD ATM LOCATION
- INSTALL NEW REPLACEMENT BIRD DETERRENT
- REPAINT STEP NOSING.

SIGNAGE / MERCHANDISING:

- REMOVE EXISTING FASCIA SIGNAGE
- INSTALL NEW 620MM HIGH INTERNALLY ILLUMINATED FASCIA WITH INTERNALLY ILLUMINATED RED LED STRIP
- REMOVE EXISTING PROJECTION SIGN
- MAKE GOOD OLD SIGNAGE AREAS AND FIXINGS NOT BEING USED

Notes:

This drawing is the copyright and property of RBSG.
It must not be copied or published without written consent.
Do not scale from this drawing except for planning purposes.

LEWIS AND HICKEY
1 St. Bernard's Row
Edinburgh
EH4 1HW
Tel: 0131 343 6222
Fax: 0131 332 7332
Email: sbury@lewishicky.com

rev	description	date
A	Dims added	23.02.15

RBS
The Royal Bank of Scotland Group

project
SOUTH SHIELDS
40 KING STREET
TYNE AND WEAR, NE33 1HF

title
ELEVATION 1
KING STREET
PROPOSED

scale
1:50@A1, 1:100@A3

drn	chk	app
SS	SS	
date 04.02.15	date 23.02.15	date

consultants' drawing number
E5826-GA-E1

brand

rbs drawing number
3759

rev.
A