

# Existing Site Signage



Unit 7 Fulcrum One, Solent Way,  
Whiteley, Hants PO15 7FE  
Tel: 0845 8722 870  
Fax: 0845 8722 874  
Web: www.innovatesigns.co.uk  
Email: info@innovatesigns.co.uk

CLIENT	One Stop	REF No.	DO/----	REV	DATE	DESCRIPTION
STORE NAME	South Shields	DATE	29/06/2015	B	29/06/2015	Fascia + Window 6
EPOS CODE	----	SCALE	as detailed @ A3	-	-	-
PROJ TYPE	Relaunch	DRAWN	IW	-	-	-
PM	Dave Overton	DWG No.	B	-	-	-

This drawing is for approval purposes. Please check all details noted on the drawing including spelling, and provide written confirmation of your approval to the Innovate Signs project manager. Once approved production will commence based on the approved drawing. Any changes made after production has begun will incur an additional cost.

# Proposed Site Signage

## Item 1 - Fascia Sign

Red RAL 3020 aluminium composite fascia panels with one|stop fabricated 500mm high pod illuminated. White vinyl lettering applied direct to fascia left/right side of centre pod, externally illuminated by full length LED trough lights above.

- a. Size: 7,500mm x 600mm H x 135mm D
- b. Size: 7,500mm x 600mm H x 135mm D

## Item 2 - Window Graphics

Digitally printed window graphic internally applied to glazing. Full height graphics are required to block view to back of counter, cigarette gantry area, and back of house areas, half height graphics are required to block view to back of shelving and refrigeration units, and remainder of graphics are safety and site id related.

- 1-4. Size: 1,780mm x 1,580mm H
- 5. Size: 2,406mm x 1,584mm H
- 6. Size: 1,618mm x 1,579mm H
- 7. Size: 740mm x 1,584mm H

## Item 3 - ATM Panel

Silver dibond fret cut panel

Size: to suit area.

## Item 4 - ATM sign

White dibond fabricated signcase with intracut "free|cash withdrawals" text internally illuminated by LED's. 2 no LED downlights to be fitted to bottom return of sign to illuminate ATM area at night.

Size: 720mm W x 400mm H x 80mm D.

## Item 5 - ATM clip frame sign

Silver clip frame displaying terms and conditions information for ATM use. Required for legal purposes.

Size: 300mm x 200mm H


## Item 6 - Manifestation

PUSH/PULL manifestation

## Item 7 - Poster Frames

Lockable poster frames. Anodised silver - 2 off.

Size: 575mm x 830mm H



Front Elevation / scale 1:50 @ A3



Post Office  
'Services' need TBC

**Store Name Displayed on Graphics: Whiteleas**  
**Store Opening Hours: 6am to 11pm TBC**





Unit 7 Fulcrum One, Solent Way,  
 Whiteley, Hants PO15 7FE  
 Tel: 0845 8722 870  
 Fax: 0845 8722 874  
 Web: www.innovatesigns.co.uk  
 Email: info@innovatesigns.co.uk

CLIENT	One Stop	REF No.	DO/----	REV	DATE	DESCRIPTION
STORE NAME	South Shields	DATE	29/06/2015	B	29/06/2015	Fascia + Window 6
EPOS CODE	----	SCALE	as detailed @ A3	-	-	-
PROJ TYPE	Relaunch	DRAWN	IW	-	-	-
PM	Dave Overton	DWG No.	B	-	-	-

This drawing is for approval purposes. Please check all details noted on the drawing including spelling, and provide written confirmation of your approval to the Innovate Signs project manager. Once approved production will commence based on the approved drawing. Any changes made after production has begun will incur an additional cost.

# Fascia Sign Specification



### Technical Specification

**LED strip**  
 Latest high lighting chip technology giving 120 degree angle.  
 IP65 protected, 50,000 hours+ lamp life.  
 Full CE certification and ROHS compliant.

**Drivers**  
 Epoxy encapsulated fully isolated case with IP67 protection.  
 Constant voltage design.  
 Short circuit, over current, over voltage protection.  
 Fitted onto Kwik release slide in Gear Trays.  
 Full CE certification and ROHS compliant.

**Light Fitting**  
 Specially designed 50mm diameter aluminium extrusion supplied up to 6000mm lengths which can be joined together using cast aluminium connectors.  
 Die cast aluminium end caps.  
 Standard 300mm Kwik Fit brackets.  
 Snap-in polycarbonate 90 degree magnifying lens diffuser.



Unit 7 Fulcrum One, Solent Way,  
 Whiteley, Hants PO15 7FE  
 Tel: 0845 8722 870  
 Fax: 0845 8722 874  
 Web: www.innovatesigns.co.uk  
 Email: info@innovatesigns.co.uk

CLIENT	One Stop	REF No.	DO/----	REV	DATE	DESCRIPTION
STORE NAME	South Shields	DATE	29/06/2015	B	29/06/2015	Fascia + Window 6
EPOS CODE	----	SCALE	as detailed @ A3	-	-	-
PROJ TYPE	Relaunch	DRAWN	IW	-	-	-
PM	Dave Overton	DWG No.	B	-	-	-

This drawing is for approval purposes. Please check all details noted on the drawing including spelling, and provide written confirmation of your approval to the Innovate Signs project manager. Once approved production will commence based on the approved drawing. Any changes made after production has begun will incur an additional cost.