SPACE ARCHITECTS

06863 – CHP Boiler House and Ancillary Accommodation

External Materials Schedule

Thomas Parrish

17 April 2018

Version 01



Project number

	Location	Specification / Colour ref.
1	**Roof**	
1.1	Boiler House roof	Kingspan KS100rw / Moonstone RAL 7035
1.2	Ancillary Building roof	Single-ply membrane with loose laid roof ballast / red porphyry
1.3	Fascia	PPC Aluminium / PPC Anthracite RAL 7016
1.4	Soffit	PPC Aluminium / PPC Anthracite RAL 7016
2	**External Walls**	
2.1	Boiler House low level plinth	Clay facing brick / Atlas Smooth Blue
2.2	Boiler House external cladding	Europanel S5 composite cladding panel / Oyster RAL 7035 Vertically, Anthracite RAL 7016 laid horizontally
2.3	Boiler House flashings	PPC Aluminium / Anthracite RAL 7016
2.4	Ancillary Building low level plinth	Clay facing brick / Atlas Smooth Blue
2.5	Ancillary Building main material	StoRend Cote render system / White
3	**Curtain Walling / Windows**	
3.1	Frames	PPC Aluminium / Anthracite RAL 7016
3.2	Glass	Clear float glass (toughened where required)
3.3	Windows generally	N/A
3.4	Louvers	PPC Aluminium / Anthracite RAL 7016
3.5	Doors within curtain walling	PPC Aluminium / Anthracite RAL 7016
4	**Doors**	
4.1	Frames	PPC Steel / Anthracite RAL 7016
4.2	Glass	Clear float glass (toughened where required)
4.3	Doors generally	PPC Steel / Anthracite RAL 7016
4.4	Sectional Overhead Door	PPC Aluminium / Anthracite RAL 7016
5	**Rainwater Goods**	
5.1	Gutters, downpipes, hopper heads, accessories	PPC Aluminium / Anthracite RAL 7016

6	**External Works**	
6.1	Access Road	Concrete / Colour match existing
6.2	Ground cover between buildings	Loose laid aggregate / red porphyry
6.3	External metal work (pipe support structure)	Paint finished steel / Anthracite RAL 7016
6.4	Close board fence / Acoustic fence	Softwood / Stained