

PLANT SCHEDULE: Planting plan dwg. No. 1434-14-50.

TREES:		CG/RB/BR	Girth / Height	No.
Bp	Betula pendula	CG*	10-12cm	1
CA	Corylus avellana	CG*	10-12cm	1
ME	Malus 'Evereste'	CG*	10-12cm	2
MGH	Malus 'Golden Hornet'	CG*	10-12cm	2
MJD	Malus 'John Downie'	CG*	10-12cm	4
PA	Prunus avium	CG*	10-12cm	2
SA	Sorbus aucuparia	CG*	10-12cm	4
SKH	Syringa vulgaris 'Katherine Haverneyer'	CG*	8-10cm	2
* Air pot grown				

HEDGING:

Hedge H1: (68 linear metres) - Hornbeam hedge. 6 plants/lin. Metre in single row.

		Size	Supply Height)	No.
100%	Carpinus betulus	BR 1+2	80-100cm	408

Hedge H2: (54 linear metres) - Field Maple hedge. 6 plants/lin. metre in single row.

		Size	Supply Height)	No.
100%	Acer campestre	BR 1+1	80-100cm	324

SHRUBS / HERBACEOUS STOCK			Supply Height	No.
Am	Astrantia major	9cm pot	-	16
BSW	Berginia 'Sissinghurst White'	3L	20-30cm	45
CE	Carex 'Evergold'	3L	-	10
CCG	Chaenomeles superba 'Crimson & Gold'	10L	60-80cm	16
CaTL	Clematis alpina 'Tage Lundell'	7L	90-120cm	1
Cm	Clematis montan 'Elizabeth'	7L	90-120cm	1
CMA	Clematis 'My Angel'	7L	90-120cm	1
Ct	Clematis tangutica	7L	90-120cm	2
GAR	Geranium 'Azure Rush'	3L		67
GR	Geranium 'Rozanne'	3L	-	58
Hp	Hydrangea petiolaris	10L	60-80cm	16
Hm	Hypericum x moserianum	3L	30-40cm	64
LaM	Lavandula 'Munstead'	3L	30-40cm	32
Ob	Osmanthus burkwoodii	10L	40-60cm	6
PaS	Persicaria affinis 'Superba'	2L	-	57
Pc	Prunus x cistena	3L	40-60cm	48
SF	Spiraea 'Firelight'	3L	30-40cm	6
Si	Stephandra incisa 'Crispa'	3L	30-40cm	36
Voc	Viburnum opulus 'Compacta'	3L	40-60cm	36
WFV	Weigela 'Florida Variegata'	3L	40-60cm	8

RAIN GARDEN PLANT MATERIAL			Supply Height	No.
Ar	Ajuga reptans	9cm pot	-	8
As*	Allium sphaerocephalon	Bulbs	-	100
BCp	Berginia cordifolia 'Purpurea'	3L	15-20cm	96
MsS	Miscanthus sinensis 'Starlight'	3L	-	105
PaS	Persicaria affinis 'Superba'	2L	-	69
RfG	Rudbeckia fulgida 'Goldsturm'	3L	-	27
* Note Allium bulbs to be planted at 10cm centres within bed of Ajuga reptans				

TURF:	
To be Rolawn medallion or similar approved	228m2

KEY

- Proposed trees
- Proposed shrub / herbaceous planting
- Proposed planting to 'rain garden' areas
- Proposed turf
- Garden to be rotovated
- Gravel (oatmeal / honey colour)

NB: Rain garden beds to receive a gravel top dressing, 25mm deep. Gravel to be light / silver grey (such as Dove Grey limestone gravel, from Decorative Aggregates or similar approved), size 10mm.

Tree root barriers as per NBS specification Q31/510A

- Root barriers to be used:
- Where trees are planted within 3m of existing/proposed underground service routes.
- Where trees are planted within 2m of the edge of a footpath .NB: No trees to be planted closer than 2m to a road kerb.
- Depth of root barriers to be as follows:
- 1.5mdeep where used to protect service routes.
- 600mm deep where used to protect pedestrian kerb line.
- Trees planted within hedges which are also within 2m of footpath kerbs are to be planted within a 'root director', 600mm deep.
- Root barriers and root directors to be ribbed as supplied by Greenleaf (te. 01424 717 797).
- Root barriers to be installed with top of barrier 50mm below finished soil levels and with
- sides vertical. Overlapping to be as recommended by supplier.

COPYRIGHT © glen kemp (newcastle) ltd.

Rev	Date	Description
A	25-04-18	Additional planting added to plot 15. Turf substituted with grave. for smaller gardens, seeding omitted to rear gardens.
B	17-07-18	Species substitutions and additiona. note added.

glenkemp
LANDSCAPE ARCHITECTS
design works, william street, gateshead, NE10 0JP
tel: 0191 495 2495
email: info@glenkemp.co.uk

PROJECT
East Boldon

DRAWING TITLE
Planting Plan

CLIENT
Gentoo Homes

ISSUE PURPOSE	DRAWN	CHECKED
CONSTRUCTION	PB/QV	PB
SCALE		DATE
1:250@A1		Apr. 2018
DRAWING NUMBER		REVISION
1434-14-50		**B**