


**LEVEL 2 - FIRST FLOOR PLAN**
1:100

FORMER POOL AND CHANGING VILLAGE

NORTH

## LEGEND

Development Area Boundary
Existing Building Demolished

## WALL TYPE & FINISHES SCHEDULE

Wall ref: A - British Gypsum Classic metal stud partitioning system consisting of 146mm 'C' stud at max. 600mm ctrs. Linings per side to consist of inner layer of 15mm British Gypsum Wallboard & outer layer of 15mm British Gypsum Duraline. NBS K10-133. Finished with seamless jointing & decoration NBS M60-115.
System to include 25mm deflection head detail.

Wall ref: B - Metsec steel framing system infill to inner leaf of level 2 external wall. Consisting of 150mm wide studs at max. 600mm ctrs with 50mm Knauf Earthwool flexible slab cavity insulation NBS G10-150A and F30-155A.
Isover Vario KM Duplex vapour control layer fixed to internal side of stud NBS P10-310A
Internal linings to consist of inner layer of 15mm British Gypsum Wallboard & outer layer of 15mm British Gypsum Duraline. Duraline to be substituted for Wallboard above 2.4m high NBS K10-200, 201. Finished with seamless jointing & decoration NBS M60-115.
External lining 12mm cement fibre board NBS G10-150A

Wall ref: C - 100/140mm thk. Thomas Armstrong dense concrete NBS F10-356 with fair-faced finish and decoration to both faces, excluding external face of inner leaf cavity wall NBS M60-110A

Wall ref: D - 100/140mm thk. Thomas Armstrong dense concrete NBS F10-356 with two coat wet plaster finish to one side only NBS M20-220A and fair-faced finish to the other. Decoration to both faces NBS M60-110A

Wall ref: E - 100/140/215mm thk. Thomas Armstrong dense concrete NBS F10-356 with two coat wet plaster finish to both sides NBS M20-220A. Decoration to both faces NBS M60-110A

Wall ref: F - Two coat wet plaster to existing substrates NBS M20-215

**ISSUED FOR PLANNING APPROVAL**

| Rev | Date | Description | Chkd |
|---|---|---|---|
| D | 24.01.18 | Wall Ref B - Vapour control layer added - SAR | IS |
| C | 19.12.17 | Wall type/finishes schedule added - SAR | IS |
| B | 19.10.17 | Drwg amended following VE saving exercise - SAR | IS |
| A | 27.09.17 | Drwg amended to reflect 2017 scheme proposal - SAR | IS |

South Tyneside Council
Economic Regeneration
David Cramond - Corporate Director
Gordon House, Gordon Street, South Shields, Tyne & Wear, NE33 4JP
Telephone: (0191) 427 1717 Fax: (0191) 455 7770

Project
Swimming Pool Demolition
Temple Park Leisure Ctr
South Shields

Drawing Title
Proposed First Floor Plan
Level 2

| | | | |
|---|---|---|---|
| Drawn by | IRS | Date | Mar 13 |
| Checked by | XX | Date | --/--/-- |
| Scale | 1:100 | Size | A0 |

| Project Code | Drawing Number |
|---|---|
| AD 6177 | 17D |