

LEVEL 1 - GROUND FLOOR PLAN

1:100

FORMER POOL AND CHANGING VILLAGE

NORTH

LEGEND

- Development Area Boundary
- Existing Building Demolished

WALL TYPE & FINISHES SCHEDULE

- Wall ref: A - British Gypsum Classic metal stud partitioning system consisting of 146mm 'C' stud at max. 600mm ctrs. Linings per side to consist of inner layer of 15mm British Gypsum Wallboard & outer layer of 15mm British Gypsum Duraline. NBS K10-133. Finished with seamless jointing & decoration NBS M60-115. System to include 25mm deflection head detail.
- Wall ref: B - Metsec steel framing system infill to inner leaf of level 2 external wall. Consisting of 150mm wide studs at max. 600mm ctrs with 50mm Knauf Earthwool flexible slab cavity insulation NBS G10-150A and F30-155A. Isover Vario KM Duplex vapour control layer fixed to internal side of stud NBS P10-310A Internal linings to consist of inner layer of 15mm British Gypsum Wallboard & outer layer of 15mm British Gypsum Duraline. Duraline to be substituted for Wallboard above 2.4m high NBS K10-200, 201. Finished with seamless jointing & decoration NBS M60-115. External lining 12mm cement fibre board NBS G10-150A
- Wall ref: C - 100/140mm thk. Thomas Armstrong dense concrete NBS F10-356 with fair-faced finish and decoration to both faces, excluding external face of inner leaf cavity wall NBS M60-110A
- Wall ref: D - 100/140mm thk. Thomas Armstrong dense concrete NBS F10-356 with two coat wet plaster finish to one side only NBS M20-220A and fair-faced finish to the other. Decoration to both faces NBS M60-110A
- Wall ref: E - 100/140/215mm thk. Thomas Armstrong dense concrete NBS F10-356 with two coat wet plaster finish to both sides NBS M20-220A. Decoration to both faces NBS M60-110A
- Wall ref: F - Two coat wet plaster to existing substrates NBS M20-215

ISSUED FOR PLANNING APPROVAL

Rev	Date	Description	Chkd
D	24.01.18	Wall ref: B - Vapour control layer added - SAR	IS
C	19.12.17	Wall type/finishes schedule added - SAR	IS
B	18.10.17	Drwg amended following VE saving exercise - SAR	IS
A	26.09.17	Drwg amended to reflect 2017 scheme proposal - SAR	IS

South Tyneside Council
Economic Regeneration

David Cramond - Corporate Director
Gordon House, Gordon Street, South Shields, Tyne & Wear, NE33 4JP
Telephone: (0191) 427 1717 Fax: (0191) 455 7770

Project: Swimming Pool Demolition, Temple Park Leisure Ctr, South Shields

Drawing Title: Proposed Ground Floor Plan Level 1

Drawn by	IRS	Date	Mar 13
Checked by	XX	Date	--/--/--
Scale	1:100	Size	A0
Project Code	AD 6177	Drawing Number	016D