GS RETAIL SOLUTIONS LTD
6 THE WATER TOWER
PARKVIEW WAY
EPSOM
SURREY
KT19 8LX

Customer:	MR.RAJ
Shop Name:	BURTON'S CONVENIENCE (PREMIER)
Address:	47-55, ORMONDE STREET, JARROW, NE32 3PB
E-mail:	srretailingltd@gmail.com
Date:	13.01.2025
Project No:	47-55/NE323PB/2025/01

QUOTATION

	DESCRIPTION	PRICE	TOTAL
1	**REMOTE DISPLAY CABINET** Supply & install 1 x 7500mm Arneg Osaka 2 chillers with 1 x J & E HALL condensing unit (JEHS-0400-B3-M-3). Condensing unit will be fitted on condensing block on the floor and the pump will be fixed if required. Arneg Osaka 75/216h:base + 5x450mm shelves,Hinged Glass doors, top entry pipe-work, electronic controller, led canopy and piller lighting (UK supply and fit), including EPOS **Warranty :- 1 year warranty for parts and labour for Chillers.** **Customer responsibility is to maintain the room temperature less than 24 degree celsius at all times.** **Noise level for the condensing unit will be 38DBA in 10mt. free field conditions.**		
1	**REMOTE DISPLAY CABINET** Supply & install 1 x 2500mm Arneg Osaka 2 chillers with 1 x J & E HALL condensing unit (JEHS-0200-B2-M-3). Condensing unit will be fitted on condensing block on the floor and the pump will be fixed if required. Arneg Osaka 75/216h:base + 5x450mm shelves,Hinged Glass doors, top entry pipe-work, electronic controller, led canopy and piller lighting (UK supply and fit), including EPOS **Warranty :- 1 year warranty for parts and labour for Chillers.** **Customer responsibility is to maintain the room temperature less than 24 degree celsius at all times.** **Noise level for the condensing unit will be 38DBA in 10mt. free field conditions.**		
1	**REMOTE DISPLAY CABINET** Supply & install 1 x 5D Freezer 3898mm Arneg mini Astana with 1 x J & E HALL condensing unit (JEHS-0680-B3-M-3). Condensing unit will be fitted on condensing block on the floor and fix condensing pump if required (3 phase). **Notes:- Refrigeration carries 1 year warranty for parts and labour** **Customer responsibility is to maintain the room temp less than 24 degree celsius at all times** **Noise level for the condensing unit will be 38DBA in 10mt. free field conditions**		
1	**FLOORING** Supply & install GTI Max 625 x 625 Vinyle interlocking flooring for approximatley 140m2 shop retail area on top of the existing flooring.		
1	**LIGHTING** Supply and install 50nos.of 600x600 Led double line lights.		
1	**COUNTER** Supply and fix 5m confectionery counter with 2counter drops as per the drawing, Behind the counter woodwork, electrical work and hanex hard top with silverstone effect.		
1	**SHELVING** Supply and install Graphite Grey (Ral 7024) metal modular shelving as per the drawing. Gondola shelving will be 2.1 m.high, (Base 470mm + 5 x 470mm) & wall shelving will be 2.4m high (Base 470mm + 5 x 470mm). New 40mm Epos ticket edging will be fitted to all shelving and refrigeration.		
1	**JOINERY WORK** Supply and install promo panels, which will be done in black & red plain or slat MDF panels. Supply and install wall end panels, which will be done in black slatwall MDF panels with mirrored inserts. Cladding all corners and exposed walls will be done in black MDF panels complete with mdf corners. Cladding with black panels between ceiling & wall bay height, on top of the chillers and freezers.		
1	**REFRESH UNIT** Supply and install "2.8m refresh unit with matching colour as per the premier requirement. The unit includes durasein solid surface, 3 x cup dispensers , 2 x litter flap		

1	**FREEZER ROOM** Supply and install Freezer Room 1832mm (D) x 2500mm (W) x 2400mm (H) with the door. Supply & install aluminium floor inside the freezer room. Installing new Evaporator system inside the room and the connecting J & E Hall condensor unit (JEHS-0500-B3-M-3) will be fitted outside. **Notes:- Refrigeration carries 1 year warranty for parts and labour.** **Customer responsibility is to maintain the room temp less than 24 degree celsius at all times.** **Noise level for the condensing unit will be 38DBA in 10mt. free field conditions.** **Shelving & any accessories not included.**		
1	**CHILLER ROOM** Supply and install Chiller Room 1832mm (D) x 2500mm (W) x 2400mm (H) with the door. Supply & install floor inside the chiller room. Installing new Evaporator system inside the room and the connecting J & E Hall condensor unit (JEHS-0350-B3-M-3) will be fitted outside. **Notes:- Refrigeration carries 1 year warranty for parts and labour** **Customer responsibility is to maintain the room temp less than 24 degree celsius at all times** **Noise level for the condensing unit will be 38DBA in 10mt. free field conditions** **Shelving & any accessories not included.**		
1	**BEER CAVE** Supply and install Beer Cave 3200mm (D) x 6200mm (W) x 2400mm (H) with push door with automatic system. The floor will be covered by GTI Max flooring, installing black suspended ceiling with new lighting system. Installing new shelving inside the cave, 2 corner boxes covered with brick affect wall paper. Installing new Evaporator system inside the cave and the connecting J & E Hall condensor unit (JEHS-0500-B3-M-3) will be fitted outside. **Notes:- Refrigeration carries 1 year warranty for parts and labour** **Customer responsibility is to maintain the room temp less than 24 degree celsius at all times** **Noise level for the condensing unit will be 38DBA in 10mt. free field conditions** **Shelving & any accessories not included.**		
1	**ELECTRICITY** Supply and fit new wiring for the condensing units, supply and fit double sockets for chillers and freezers. Electrical supply will be taken from the existing wiring. Any improvement/alteration will be done at an additional cost.		
1	**SKIP** Removal and disposal of rubbish with a skip hire		
	It will be customer's responsibility to get all the necessary planning permission from the relevant authorities. **This quotation does not covers the following:-** *** Shop front, shutters, signage** *** Building works** *** Air conditioning Units** *** Epos Till**		
			£132,450.00
		VAT	£26,490.00
		TOTAL	**£158,940.00**

Thank you

Customer's Approval
I here by approve this quotation and acknowledge the details shown are correct.

Customer's Signature : _____ Witness Signature : _____

Customer's Name : _____ Witness Name : _____