This drawing is copyright.
It is sent to you in confidence and must not be reproduced or disclosed to third parties without our prior permission.
Do not scale from this drawing.
This drawing is to be read in conjunction with all relevant consultants, specialist manufacturers drawings and specifications.
Any discrepancies in dimensions or details on or between these drawings should be drawn to our attention.
All dimensions are in millimeters unless noted otherwise.
Any surveyed information incorporated within this drawing cannot be guaranteed as accurate unless confirmed by fixed dimension.

REV	DESCRIPTION	BY	CHKD	DATE
P01	Tender Issue	DJP	KH	16/07/2024
P02	Tender Issue	DJP	KH	19/07/2024
P03	Fencing and gates to be removed added to drawing	DJP	KH	04/09/2024
P04	SPECIFICATION NOTES EXPANDED	DJP	KH	09/09/2024
P05	Height of Accoustic Fence increased to 4m	DJP	KH	14/11/2024
C01	Construction Issue	DJP	KH	27/02/2025
C02	Background updated for Planning	DJP	KH	11/04/2025

concrete road

silver birch

Tree Top Level

MH

PST3

PST4

PST2

PST12

PST11

PST14

Post

MH (Collapsed)

SALT BARN

CHAPTER 8 STORAGE

MESH STORAGE

BARRIER STORAGE

LOADING BAY
(Refer to Struc. Eng Drawings)

LOADING RAMP
(refet to Struc. Eng drawings)

concrete road

FUEL ST. AREA

SKIPS

GRITTER PARKING

G2 G1 G4 G3 G6 G5

F3 F4 F5 F6 F7 F8 F9 F10

CONTAINER AREA
(20ft x 8ft)

GUARDRAIL STORAGE 70m2

FLAG RAMP
(Refer to Struc. Eng Drawings)

F2 FLEET PARKING F1

STORAGE
(28x9m)

BIN AREA

tap

OFFICE
(GIA 20.95m x 8.36m = 175m²
Refer to drawings 01 - 2000, 2001 & 2100)

F11

BIKE AREA
(X3 Sheffield Cycle Stands, for X6 Cycles)

S1 S5 S10 S15

STAFF CAR PARK

S25 S20 S16 M/C

BT

LP

B1297 Blackett Street

B1297 Blackett Street

0 5 10 20
1:200 Scale Bar (m.)

FENCING AND GATE KEY:-

- EXISTING SECURITY PALISADE FENCING 2m HIGH
- NEW SECURITY PALISADE FENCING 2m HIGH BY HERMEQ OR SIMILAR, GALVANISED FINISH TO MATCH EXISTING WITH PALISADE ULTRA PALES WITH BOLT HEAD PROTECTION, ULTRA POSTS @ 2750mm CENTRES WITH TOP RAIL AND BOTTOM RAIL, EACH RAIL CONNECTED WITH M12 ANTI VANDAL FIXINGS, POSTS SET IN CONCRETE FOUNDATIONS.
- EXISTING FENCING
- EXISTING FENCING & GATES TO BE REMOVED
- NEW 5mm THICK WIRE WELDMESH FENCING 2m HIGH TO BE SAFEMESH 100 BY HERMEQ OR SIMILAR, POWDER COATED GREEN FINISH, WITH SAFEMESH 60x60mm STANDARD POSTS AT 3.03m CENTRES, POSTS SET IN CONCRETE FOUNDATIONS
- NEW 3m HIGH REFLECTIVE COMPOSITE ACOUSTIC FENCING, COMPRISING LOOSE COMPONENTS FOR ASSEMBLY ON SITE: PANELS COMPRISING 225x45mm REFLECTIVE HORIZONTAL BOARDS WITH H PATTERN COVER STRIPS, 2 OFF VERTICAL BEARERS PER POST, 2 OFF SEALS PER POST IN GREY FINISH. POSTS - 152x89x16ub x 4000mm LONG, GALVANISED FINISH SET INTO CONCRETE FOUNDATIONS, FENCING BY BOUNDARY SERVICES LTD - TEL 01902 790502
- NEW 4m HIGH REFLECTIVE COMPOSITE ACOUSTIC FENCING, COMPRISING LOOSE COMPONENTS FOR ASSEMBLY ON SITE: PANELS COMPRISING 225x45mm REFLECTIVE HORIZONTAL BOARDS WITH H PATTERN COVER STRIPS, 2 OFF VERTICAL BEARERS PER POST, 2 OFF SEALS PER POST IN GREY FINISH. POSTS - 152x89x16ub x 5000mm LONG, GALVANISED FINISH SET INTO CONCRETE FOUNDATIONS, FENCING BY BOUNDARY SERVICES LTD - TEL 01902 790502
- NEW 2m HIGH REFLECTIVE COMPOSITE ACOUSTIC FENCING, COMPRISING LOOSE COMPONENTS FOR ASSEMBLY ON SITE: PANELS COMPRISING 225x45mm REFLECTIVE HORIZONTAL BOARDS WITH H PATTERN COVER STRIPS, 2 OFF VERTICAL BEARERS PER POST, 2 OFF SEALS PER POST IN GREY FINISH. POSTS - 127x76x13UB x 2000mm LONG, GALVANISED FINISH WITH BASE PLATE APPLICATION TO FIX TO TOP OF NEW CONCRETE WALL, FENCING BY BOUNDARY SERVICES LTD - TEL 01902 790502
- PEDESTRIAN SAFETY BARRIER / GUARDRAIL, GALVANISED FINISH, 1000mm HIGH BY GRAMM BARRIER SYSTEMS OR SIMILAR
- 200mm x 25mm TREATED SW KICKER FIXED TO SAFETY BARRIER

(A) DOUBLE GATES TO EXISTING CARRIAGEWAY WIDTH
(B) 6m WIDE DOUBLE GATES - 3m high
(C) 1m WIDE PEDESTRIAN GATE - 2.1m high (where this falls in a higher fence, a fixed panel over is provided)
(D) 1m WIDE PEDESTRIAN GATE (ACCESS CONTROL)

GENERAL NOTE:
ALL GATES ARE TO BE IN SAME MATERIAL AS FENCE THEY ARE SITUATED WITHIN

PURPOSE:	CONSTRUCTION
PROJECT:	MIDDLEFIELDS DEPOT JARROW SOUTH TYNESIDE COUNCIL
DESCRIPTION:	PROPOSED SITE PLAN - VENJ SHOWING PROPOSED FENCING

DRAWN BY:	SCALE:	SHEET SIZE:	DATE:
JL	1:200	A0	16/07/24

PRO. NO:	ORIG:	VOLUME:	LEVEL:	TYPE:	ROLE:	NUMBER:	SUITABILITY:	REV:
23089	HL	ZZ	ZZ	DR	A	2301	D2	C02

HOWARTH LITCHFIELD
Liddon House, Belmont Business Park, Durham. DH1 1TW.
Tele: (0191) 3849470 E: hlp@hlpuk.com www.howarthlitchfield.com

© Copyright and all intellectual property rights remain vested in Howarth Litchfield Partnership Limited